

United States Department of the Interior
National Park Service

For NPS use only

**National Register of Historic Places
Inventory—Nomination Form**

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic Girard Carnegie Library

and or common Same

2. Location

street & number 128 W. Prairie

 not for publication

city, town Girard

 vicinity of

state Kansas

code 20

county Crawford

code 037

3. Classification

Category	Ownership	Status	Present Use	
<u> </u> district	<u> X </u> public	<u> X </u> occupied	<u> </u> agriculture	<u> </u> museum
<u> X </u> building(s)	<u> </u> private	<u> </u> unoccupied	<u> </u> commercial	<u> </u> park
<u> </u> structure	<u> </u> both	<u> </u> work in progress	<u> X </u> educational	<u> </u> private residence
<u> </u> site	Public Acquisition	Accessible	<u> </u> entertainment	<u> </u> religious
<u> </u> object	<u> N/A </u> in process	<u> X </u> yes: restricted	<u> </u> government	<u> </u> scientific
	<u> N/A </u> being considered	<u> </u> yes: unrestricted	<u> </u> industrial	<u> </u> transportation
		<u> </u> no	<u> </u> military	<u> </u> other:

4. Owner of Property

name City of Girard

street & number City Hall

city, town Girard

 vicinity of

state Kansas 66743

5. Location of Legal Description

courthouse, registry of deeds, etc. Crawford County Clerk

street & number Crawford County Courthouse

city, town Girard

state Kansas 66743

6. Representation in Existing Surveys

title N/A

has this property been determined eligible? yes X no

date N/A

 federal state county local

depository for survey records N/A

city, town N/A

state N/A

7. Description

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

The Girard Carnegie Library (c. 1906) is located at 128 W. Prairie in Girard, Crawford County, Kansas (pop. 2,888). The one-story, rusticated cement block, Neo-Classical building stands on a corner lot one block west of Girard's County Courthouse Square. Its facade orientation is south. The building measures approximately fifty-eight feet from east to west and thirty-six feet from north to south. The building retains its original function as a library.

The one-story, grey cement block building sits on a rusticated cement block, raised foundation. It is a rectangular structure with a truncated hipped roof. Three bays comprise the building's facade and rear, it is one bay deep. A parapetted, entry pavilion projects from the facade's center bay. The roof is covered with asphalt shingles. A limestone water table course runs above the foundation windows. Limestone quoins ornament the building's corners.

The projecting entryway pavilion contains a recessed doorway with a replacement aluminum doorframe. The original door treatment appears to be double wood and glass doors with sidelights and a transom. A limestone lintel surmounts the doorway. Limestone, Ionic columns stand in antis inside the pavilion, supporting a multiply moulded, Classical wooden architrave. This architrave continues around the entire building. A modillioned wooden cornice projects out from a cement block frieze, this treatment continues around the entire building. The pavilion's stepped, parapet holds a limestone tablet bearing the carved "19 Carnegie Library 06" and limestone cartouche above that. Steps lead up to the doorway. They do not appear to be the original steps and are not flanked by limestone abutments. The openings in the pavilion's east and west walls are filled in with corrugated plastic.

The building's fenestration on the first level is 1/1 double hung with transoms. Limestone lintels surmount the windows, limestone jack arches with keystones surmount the transoms, and limestone sills underscore the windows. The windows and transoms are aluminum replacements. Four windows pierce the facade, three windows apiece pierce the east and west elevations, and five windows pierce the north elevation. One-over-one double hung aluminum windows pierce the building's foundation below the first level windows. Limestone lintels surmount the above grade windows. A basement door pierces the foundation wall on the western elevation's foundation wall. An original door on the elevation's foundation wall has been closed for a window.

The interior of the library maintains its original three-bay floorplan with a vestibule entrance. The first floor ceiling has been covered with dropped acoustic tiles. The interior woodwork, such as door and window surrounds, is retained.

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input checked="" type="checkbox"/> education	<input type="checkbox"/> military	<input checked="" type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates c. 1906 **Builder/Architect** Hair and Smith - Architects

Statement of Significance (in one paragraph) A.H. Ritter - Builders

The Girard Carnegie Library (c. 1906) is being nominated to the National Register as part of the Carnegie Libraries of Kansas thematic resources nomination (c. 1902-1921) at the local level of significance under criteria A and C for its historical association with the Carnegie Corporation Library Building Program and for its architectural significance as a new building type. A library association was organized in Girard in 1899. The community received their \$8,000.00 Carnegie Library grant in 1905, library construction was completed in 1906. The Girard Carnegie Library is an example of the Neo-Classical style.

Sixty-three Carnegie funded libraries were built in Kansas during the first three decades of the Twentieth Century; four of these libraries were built on college campuses. In most cases, the Carnegie funded library represented the community's first library building although many Kansas communities had book clubs and library organizations well before the Carnegie Corporation Library Building Program was founded. In the case of the four college libraries, the building represented the first structure which was solely devoted to housing the institution's books and providing study space. Carnegie did not solicit interest in the program, with the exception of the Anderson (Carnegie) Memorial Library which was built by Carnegie as a memorial to his friend John Anderson and was the first college library nationally to receive Carnegie funding. Communities initiated contact with the corporation by letter, indicating their desire for a Carnegie funded library. If the Corporation responded favorably to the request, a firm local commitment to the program's requirements, which generally resulted in a public election in support of the library, followed. Obviously these actions represented a perceived need within the community for a library building and the Carnegie Corporation Library Building Program represented an excellent way to secure the funds to build one. Many of the Carnegie Libraries built in Kansas reflect the high space utilization design guidelines promoted by the Carnegie Corporation after 1910, underscoring the point that before the Carnegie Corporation Library Building Program, few architects and/or builders had experience designing this building type.

Twenty-eight Carnegie Libraries are included in this nomination (see inventory). Twelve Carnegie Libraries have been listed individually on the National Register: Argentine, Case Library (Baker University, Baldwin City), Caldwell, Dodge City, Emporia, Goodland, Lawrence, Leavenworth, Newton, Ottawa, Parsons, and Pittsburg. The Carnegie Library at Arkansas City is included in a downtown historic district. Thirteen Carnegie Libraries have been demolished: Great Bend, Halstead, Hays, Iola, Kansas City, McPherson, Morrison Library (Fairmont College, Wichita), Olathe, Osawatimie, Plainville, Russell, Salina, and Washington. Five Carnegie Libraries have been altered enough to make them ineligible for the National Register: Abilene, Garden City, Hiawatha, Lyons, and Stockton. (The nominations for the Concordia, Eureka, Independence, and Winfield libraries were deferred.) Twenty-two of the nominated libraries retain their original function. All of the buildings are in use or have an active use planned for them. The

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Continuation sheet 1

Item number 8

Page 1

nominated libraries maintain a high to moderate degree of architectural and structural integrity.

Industrialist Andrew Carnegie (1835-1919) and the Carnegie Corporation significantly influenced the development and expansion of public library systems worldwide. Between 1886 and 1921 Carnegie funds assisted in the construction of 1,681 city and 108 college libraries in the United States. As a region, the Mid-West, Kansas included, did not have a well established public library system until the Carnegie Program and ranks highest in the number of communities which obtained Carnegie Libraries nationwide. Out of the forty-six states to participate in the library building program, Kansas ranks approximately eleventh in the number of Carnegie Libraries built. For many Kansas communities, the Carnegie Library represented its first library building, providing an environment that all members of the community could share for the purposes of reading, learning, and education.

Eligibility for Carnegie Library funds rested on several factors. Firstly, the population of the community had to exceed 1,000; in Kansas this indicated at least a second class city status. This population requirement generally resulted in county seat communities applying for and receiving Carnegie Libraries. Some communities with populations less than 1,000 banded together with neighboring communities to achieve the 1,000 mark and applied for township libraries, as in the case of the Peabody and Canton Township libraries. In the case of college libraries this constraint may not have applied, although the four Kansas colleges to receive Carnegie libraries were located in cities which had populations in excess of 1,000 by 1900. Secondly, the applicant had to provide a site for the library. The sites tended to be one or two blocks outside of the community's main business district. Thirdly, the applicant had to provide an annual endowment for the maintenance and improvement of the library which amounted to at least ten percent of the initial grant from the Carnegie Corporation.

This last factor contributed to the ending of the Carnegie Library Building Program in 1917, although grants for books and other improvements continued for several more decades. An inherent problem for second class cities in Kansas was the .4 mill levy restriction for libraries, making it difficult for some communities to meet the annual ten percent maintenance appropriation solely through public dollars. In 1917 the Kansas State legislature increased the library levy to .5 mill for second and third class cities, an amendment which affected most of the communities in the State that had Carnegie Libraries. In 1916, large communities such as Topeka, Wichita, Hutchinson, and Leavenworth had library mill levies of 1.06, 1.2, 1.8, and 3.5 respectively. In Kansas, the average public library grant was \$12,000 and the average college library grant was \$37,000. These monies covered the cost of the building, the necessary furniture and fixtures, and the architects' fees.

Prior to 1910, the Carnegie Corporation did not provide design guidelines for the libraries that it funded and because the library was a relatively new building type, few architects and/or builders had experience with its design. Many of the early libraries were expensive examples of the Beaux Arts style with little focus on floor plan and space

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only

received

date entered

Continuation sheet 2

Item number 8

Page 2

efficiency. In 1910, Carnegie's personal secretary James Bertram developed model specifications and floorplans for proposed libraries, entitling his work Notes on Library Buildings. The Notes on Library Buildings provided the first widely circulated guidelines for library design in this country.

Bertram wrote:

Small libraries should be pland (sic) so that one librarian can oversee the entire library from a central position.... The bilding (sic) should be devoted exclusively to: (main floor) housing of books and their issue for home use; comfortable accomodations for reading them by adults and children; (basement) lecture room; necessary accommodation for heating plant; also all conveniences for the library patrons and staff. Experience seems to sho (sic) that the best results for a small general library are obtained by adopting the one-story and basement rectangular type of bilding (sic), with a small vestibule entering into one large room sub-divided as required by means of bookcases.... The rear and side windows may be kept about six feet from the floor, to giv (sic) continuous wall space for shelving. A rear wing can be added for stack-room (when future need demands it) at a minimum expense, and without seriously interfering with the library servis (sic) during its construction. The site chosen should be such as to admit lite (sic) on all sides, and be large enuf (sic) to allow extension, if ever such should become necessary.

The thirty-six Carnegie Libraries built in Kansas after 1910 reflect Bertram's precedents, exhibiting high space utilization, and often including full basements, although the raised basement is a design element employed in the earlier libraries as well. Most of these one-story libraries exhibit a three bay, Neo-Classical facade with a projecting central pedimented entry pavilion and are one bay deep. The use of native limestone is evident in some of the libraries but the most common material combination is brick with a limestone foundation. While there is some tendency toward a vernacular interpretation to the design ornamentation of these libraries, the general approach verges on high style.

Correspondence between the Carnegie Corporation and the library boards from the Kansas communities that received Carnegie Libraries indicates that the designs for these libraries were carefully scrutinized by Bertram and in many cases, were resubmitted several times before meeting his requirements. Upon the completion of a library, the library board was instructed to send a full set of blueprints and elevations of the building to the Corporation. However, recent correspondence between the Kansas State Historical Society and the Carnegie Corporation reveals that the Corporation does not have blueprints of the Kansas libraries. The Corporation does have some library photographs but the collection is not inclusive.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only

received

date entered

Continuation sheet 3

Item number 8

Page 3

Three architects were particularly active in the design of Kansas Carnegie Libraries: George P. Washburn of Ottawa, Kansas designed nine, A. T. Simmons of Bloomington, Illinois designed six, and William Warren Rose of Kansas City, Kansas designed four. Washburn's libraries are primarily of the standard three-bay, Neo-Classical variety. His firm is credited with the Carnegie libraries in Burlington, Canton, Cherryvale, Columbus, Eureka, Halstead, Osawatomie, Ottawa, and Sterling. Simmons engaged in a more eclectic approach, designing libraries in Abilene, Chanute, Council Grove, Downs, Hays and Yates Center. Rose is credited with the classically inspired libraries in Argentine, Kansas City, Manhattan, and Newton. In Kansas, many Kansas based architects were commissioned to design Carnegie Libraries as well as architects from Illinois, Missouri, Nebraska, and Texas.

Today, many of the state's Carnegie Libraries are facing serious space shortages. The alternatives of adding on or vacating both present preservation problems. Additions to these libraries must be such that the building's original character is not altered. Vacating the library for a larger facility leaves the problem of an empty building, in some communities county historical societies have inherited the empty Carnegie Library. In any event, when these buildings are no longer recognized from a design standpoint as Carnegie Libraries, their architectural significance ceases.

Inventory of Carnegie Libraries in Kansas

<u>SITE</u>	<u>DATE</u>	<u>INVENTORY NUMBER</u>
1. Anthony Public (Carnegie) Library (Harper County) 104 N. Springfield Anthony, Kansas 67003 Owner: City of Anthony Lots 22,23,24; Block 34.	c. 1911	⁰⁰⁰⁴ 77-0180-0003
2. Burlington Carnegie Free Library (Coffey County) 201 N. Third Burlington, Kansas 66839 Owner: City of Burlington Lots 8,9; Block 35.	c. 1912	31-0690-0015
3. Canton Township Carnegie Library (McPherson County) Box 336 Canton, Kansas 67428 Owner: Canton Township Lots 7,8,9,10,11; Block 2.	c. 1921	113-0790-0001
4. Chanute Public (Carnegie) Library (Neosho County) 102 S. Lincoln Chanute, Kansas 66720 Owner: City of Chanute Lots 2,3; Block 39.	c. 1906	133-0870-0067
5. Cherryvale Public (Carnegie) Library (Montgomery County) 329 E. Main Cherryvale, Kansas 67335 Owner: City of Cherryvale Lots 7,8; Block 39.	c. 1913	⁰⁹³⁰⁻⁰⁰⁰⁵ 125-0939-0006
6. Clay Center Carnegie Library (Clay County) 706 Sixth Street Clay Center, Kansas 67432 Owner: City of Clay Center Lots 12,13; Block 36.	c. 1912	27-0980-0008

- | | | |
|--|----------------|--|
| <p>7. Coffeyville Carnegie Public Library Building
 (Montgomery County)
 415 West 8th
 Coffeyville, Kansas 67337
 Owner: City of Coffeyville
 Lots 7,8; Block 47.</p> | <p>c. 1912</p> | <p>¹⁰⁵⁰
 125-2670-0019</p> |
| <p>8. Columbus Public (Carnegie) Library (Cherokee County)
 205 N. Kansas
 Columbus, Kansas 66725
 Owner: City of Columbus
 Lots 9,10; Block 9.</p> | <p>c. 1913</p> | <p>21-1100-0008</p> |
| <p>9. Council Grove (Carnegie) Library (Morris County)
 303 W. Main Street
 Council Grove, Kansas 66846
 Owner: City of Council Grove
 Lots 1,2,3; Block 19.</p> | <p>c. 1917</p> | <p>127-1180-0074</p> |
| <p>10. Downs Carnegie Library (Osborne County)
 504 S. Morgan
 Downs, Kansas 67437
 Owner: City of Downs
 Lots 8-12; Block 28.</p> | <p>c. 1906</p> | <p>141-1400-0002</p> |
| <p>11. El Dorado Carnegie Library Building (Butler County)
 101 S. Star
 El Dorado, Kansas 67042
 Owner: Dean Seeber
 N 4' Lot 3, Lot 4; Block 4.</p> | <p>c. 1912</p> | <p>15-1540-0004</p> |
| <p>12. Anderson (Carnegie) Memorial Library (Lyon County)
 The Way College of Emporia
 1300 West 12th Avenue
 Emporia, Kansas 66801
 Owner: Way College of Emporia
 Located on the Way College of Emporia campus.
 SW, NE1/4, Sec. 9, T19, R11, E. of the 6th p.m.,
 running thence E. 76 rods, thence N. 80 rods,
 thence W. 76 rods, thence S 80 rods to the</p> | <p>c. 1902</p> | <p>111-1660-0002</p> |

Anderson (Carnegie) Memorial Library (Lyon County) cont.

place of beg., except a tract beg. at the S,SW1/4
Sec. 9, thence N. 670 ft., thence E. 540 ft.,thence
S. 250 ft, thence W. 374 ft., thence S. 420 ft.,
thence W. 166 ft. to the point of beg. in Lyon Co.,KS
and Lots Numbered 61,63,65,67,71, and the N. 30 ft. of
Lot F all in Block numbered 3, in College Hill Addition
to the City of Emporia.

- | | | |
|---|------------------|---------------|
| 13. Fort Scott Public (Carnegie) Library (Bourbon County)
201 South National
Fort Scott, Kansas 66701
Owner: City of Fort Scott
Lots 1,(N1/2) 3; Block 123 | c. 1902 | 11-1830-0016 |
| 14. Girard Carnegie Library (Crawford County)
128 W. Prairie
Girard, Kansas 66743
Owner: City of Girard
Lots 17,18; Block 14. | c. 1906 | 37-2050-0003 |
| 15. Herington Carnegie Public Library (Dickinson County)
102 S. Broadway
Herington, Kansas 67449
Owner: City of Herington
Lots 2,4; Block 40. | c. 1915 | 41-2420-0006 |
| 16. Hutchinson Public (Carnegie) Library Building-
Labor Temple (Reno County)
427 N. Main
Hutchinson, Kansas 67501
Owner: Hutchinson Labor Building Association
Lots 13,14,15; Block 17. | c. 1903-
1904 | 155-2660-0011 |
| 17. Kingman Carnegie Library (Kingman County)
455 N. Main
Kingman, Kansas 67068
Owner: City of Kingman
Lots 101,103,105; Original Town. | c. 1914 | 95-2850-0006 |

- | | | |
|---|---------|---------------|
| 18. Lincoln Carnegie Library (Lincoln County)
203 S. Third
Lincoln, Kansas 67455
Owner: City of Lincoln
Lot 7; Block 32. | c. 1914 | 105-3189-005 |
| 19. Lyndon Carnegie Library (Osage County)
127 E. Sixth, P.O. Box 563
Lyndon, Kansas 66451
Owner: Valleybrook Township
Lots 4-9; Block 22. | c. 1911 | 139-3360-0003 |
| 20. Manhattan Carnegie Library Building (Riley County)
Fifth and Poyntz
Manhattan, Kansas 66502
Owner: Riley County Board of Commissioners
Lot 413; Ward 2. | c. 1904 | 161-3490-0016 |
| 21. Osborne Public (Carnegie) Library (Osborne County)
Third and Main
Osborne, Kansas 67473
Owner: City of Osborne
All of Block 12. | c. 1913 | 141-4230-0006 |
| 22. Oswego Public (Carnegie) Library (Labette County)
704 Fourth Street
Oswego, Kansas 67356
Owner: City of Oswego
Lots 1,2,3,4; Block 32. | c. 1912 | 99-4250-0010 |
| 23. Peabody Township Carnegie Library (Marion County)
214 Walnut
Peabody, Kansas 66866
Owner: Peabody Township
Lots 80,82,84 on Walnut. | c. 1914 | 115-4410-0024 |
| 24. Sterling Free Public (Carnegie) Library (Rice County)
132 N. Broadway
Sterling, Kansas 67579
Owner: City of Sterling
Lots 182,184,186,188 on Broadway. | c. 1917 | 159-5225-0006 |

- | | | |
|---|---------|---|
| 25. Washburn University Carnegie Library Building
(Shawnee County)
(Education Building)
Topeka, Kansas 66621
Owner: Washburn University of Topeka
SW1/4, NW 1/4, NE 1/4, SW1/4, S1,T12, R15E | c. 1904 | 177-5400-0017 |
| 26. Wellington Carnegie Library (Sumner County)
121 W. Seventh
Wellington, Kansas 67152
Owner: City of Wellington
Lots 13,14,15,16,17; Block 53. | c. 1916 | 191-5730- ⁰⁰¹³ 0012 |
| 27. Wichita City (Carnegie) Library Building
(Sedgwick County)
220 S. Main Street
Wichita, Kansas 67202
Owner: City of Wichita
Lots 24,26,28,30,32,34,36 & 1/2 Vac. Alley Adj.
on E. & Vac. Alley Ly. N. Lot 24 Exc. Beg. SE Cor.
Lot 34 W 33.98 Ft. N. 100.56 Ft. W. 16.75 Ft. N. 9 Ft.
Nwly. 15.36 Ft. W. 6.5 Ft. N. 10 Ft. W. 49 Ft. S. 25
Ft. W. 25 Ft. N. 58.66 Ft. E. to Cen. Li. Vac. Alley
on E. Th. S. 115.56 Ft. W. 8 Ft. to SE Cor. Lot 30 S.
to Beg. Main St. Greiffenstein's Add. | c. 1915 | 173-5880-0004 |
| 28. Yates Center (Carnegie) Library (Woodson County)
218 N. Main
Yates Center, Kansas 66783
Owner: City of Yates Center
Lots 4,5,6; Block 27. | c. 1912 | 207-6010-0007 |

9. Major Bibliographical References

See attached sheet.

10. Geographical Data

Acreage of nominated property Less than 1 acre

Quadrangle name Girard

Quadrangle scale 1:24,000

UTM References

A

1	5
---	---

3	3	6	9	4	0
---	---	---	---	---	---

4	1	5	2	8	8	0
---	---	---	---	---	---	---

Zone Easting Northing

B

--	--

--	--	--	--	--	--

--	--	--	--	--	--

Zone Easting Northing

C

--	--

--	--	--	--	--	--

--	--	--	--	--	--

D

--	--

--	--	--	--	--	--

--	--	--	--	--	--

E

--	--

--	--	--	--	--	--

--	--	--	--	--	--

F

--	--

--	--	--	--	--	--

--	--	--	--	--	--

G

--	--

--	--	--	--	--	--

--	--	--	--	--	--

H

--	--

--	--	--	--	--	--

--	--	--	--	--	--

Verbal boundary description and justification The nominated property is located on Lots 17, 18; Block 14 in Girard, Kansas. The rectangular tract is bounded to the south by West Prairie, to the west by Osage Street, and to the north and east by adjacent property lines.

List all states and counties for properties overlapping state or county boundaries

state N/A code N/A county N/A code N/A

state N/A code N/A county N/A code N/A

11. Form Prepared By

name/title Martha Gray Hagedorn, Architectural Historian

organization Kansas State Historical Society date April 7, 1987

street & number 12 West 10th Street telephone 913-296-5264

city or town Topeka state Kansas 66612

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

 national state X local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature 

title Executive Director, Kansas State Historical Society date April 7, 1987

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Continuation sheet

4

Item number

9

Page

1

Carnegie Library Bibliography:

Anderson, Florence. Carnegie Corporation Library Program, 1911-1961.
(New York: Carnegie Corporation, 1963).

Bertram, James. Notes on Library Building. (New York: Carnegie Corporation, 1910).

Bobinski, George S. Carnegie Libraries: Their History and Impact on American Public Library Development. (Chicago: American Library Association, 1969).

Carnegie Corporation. Micro-film reels of correspondence between the Corporation and Kansas Carnegie Library Communities, 1902-1921. Carnegie Corporation of New York.


Gardiner, Allen. The Carnegie Legacy in Kansas: A Retrospective View of the 59 Public Libraries Built by Andrew Carnegie; A Souvenir Publication to Commemorate the Sequicentennial of Carnegie's Birth. (Topeka: Kansas State Library, 1985).

_____. Kansas Public Libraries from Abilene to Zenda. (Topeka: Kansas State Library, 1982).

Koch, T. W. A Book of Carnegie Libraries. (New York: H. W. Wilson, 1917).

State of Kansas. Session Laws, 1917. Chapter 113. "Limiting Tax Levies in Cities of the Second and Third Class."

Topeka Capital Journal, 20 December 1916; 26 December 1916.



Mapped, edited, and published by the Geological Survey
in cooperation with State of Kansas agencies


Control by USGS and USC&GS

Topography by photogrammetric methods from aerial
photographs taken 1961. Field checked 1964

Polyconic projection. 1927 North American datum
10,000-foot grid based on Kansas coordinate system, south zone
1000-meter Universal Transverse Mercator grid ticks,
zone 15, shown in blue

Red tint indicates area in which only landmark buildings are shown

Fine red dashed lines indicate selected fence and field lines where
generally visible on aerial photographs. This information is unchecked



UTM GRID AND 1964 MAGNETIC
DECLINATION AT CENTER OF

(CHECKED 11-6-2500)
1000 V

Girard Carnegie Library
Girard, Kansas
c. 1906
Kansas State Historical Society
South Facade, North view
1 of 5

Girard Carnegie Library
Girard, Kansas
Martha Hagedorn
April, 1986
Kansas State Historical Society
South Facade, North view
2 of 5

Girard Carnegie Library
Girard, Kansas
Martha Hagedorn
April, 1986
Kansas State Historical Society
South Facade, West elevation, NE view
3 of 5

Girard Carnegie Library
Girard, Kansas
Martha Hagedorn
April, 1986
Kansas State Historical Society
West elevation, East view
4 of 5

Girard Carnegie Library
Girard, Kansas
Martha Hagedorn
April, 1986
Kansas State Historical Society
North & East elevations, SW view
5 of 5

